



4441 Six Forks Road
Suite 106 #184
Raleigh, NC 27609

919.818.0413
800.689.LAKE (5253)
info@aquadocinc.com

Submitted To: Suncrest Village
Raleigh, NC 27616

Date: March 28, 2023

info@aquadocinc.com

Start Work: 2023

The following proposal, when signed by both parties, constitutes a contract for the work described below:

Inspection Repairs

Phase 2

- SCM 1 | Underground Detention:
 - The accumulated sediment will be removed from the underground pipe
 - The access lids will be adapted to improve access to the devices
 - The trash and debris will be removed from the device
 - The overgrown vegetation around the drop inlet will be cut and removed
 - All organic debris will be cleared from the drop inlet

Phase 3

- SCM 1 | Underground Detention:
 - The accumulated sediment will be removed from the underground pipe
 - All trash and organic debris will be removed from the drop inlet boxes
- SCM 2 | Grass Swale:
 - All bare areas will be remediated with grass seed and erosion control matting
 - All trash, leaf litter, and organic debris will be removed from the drop inlet grate and drop box

All areas disturbed during construction will be stabilized with seed, wheat straw and/or erosion control matting

PROGRAM TOTAL: \$6,437.50

Payment Terms: Balance due upon completion. Finance charges of 1.5% per month shall apply to all invoices past 30 days.
The above prices, specifications and conditions are satisfactory and hereby accepted. AQUA DOC is authorized to complete this contract as specified.
This contract may be withdrawn if not accepted within 30 days. All projects shall be done with weather and temperature conditions permitting.

Please sign and return contract.

Customer Signature
Ross Dion

AQUA DOC

Date
3/28/2023

Date