

Services Proposed For: Suncrest Village HOA

Suncrest Village HOA
6527 Grassy Knoll Ln.
Raleigh, NC 27616

Internal RO#: RO_16368

Driver for Corrective Action

 Attention Needed

 Action Needed

 Action Required



Compliance: _ per request from annual structural SCM inspection report cleaning sediment from the stormwater structures, clearing or debris from around the top of structure covers, adding mats and grass seed to the bare areas of the swale

Summary of Issues

Per request from annual structural SCM inspection report cleaning sediment from the stormwater structures, clearing or debris from around the top of structure covers, adding mats and grass seed to the bare areas of the swale.

Root Cause

Rainwater, snow melt runoff and vehicles carry silt and sediment to be deposited and accumulate within the trench drain and catch basin. This sediment needs to be regularly removed for the stormwater system to work properly.

Scope of Work

AQUALIS will provide the Services and Deliverable(s) as follows:

Mobilization:

- Mobilize all equipment and labor to the site
- Deploy temporary traffic cones as necessary for crew and customer safety
- Use confined space entry practices to remove accumulated sediment from SCM1 & 2 as well as UGD 1&2
- Flex hose is needed to reach the structures
- Use hand tools and brush trimmer to remove leaves and vegetation from around the structure covers
- Install mats and grass seed in bare areas of drainage swale

Demobilize:

- General site clean-up
- All sediment will be removed from the property and taken to a proper disposal facility.

Special Project Notes

This proposal is valid for 30 days

Cleaning Cost: \$2,500.00

Material Cost: \$300.00

Total Cost: \$2,800.00

Signed: _____
Suncrest Village HOA Authorized Signature

Date: _____

Signed: *Michael McManus*
Aqualis Authorized Signature

Date: 2/24/2023

